

5-29

To: 1 031011
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,273-0000
App. W/2
NW NW, SEC. 15, T 27 S, R 20 W/E
4260 feet from S section line
4560 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4243
Operator: Cross Bar Petroleum, Inc.
Name & Address: P.O. Box 20080
Wichita, KS 67208

Lease Name Breensing Well # 16-2
County Kiowa 177.94
Well Total Depth 5475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 461

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address 2759 South Broadway, Wichita, KS 67216

Company to plug at: Hour: 2 a.m. Day: 29 Month: 5 Year: 19 89

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1282-1301'

1st plug at 1290' with 50 sx cement, 2nd plug at 470' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 29 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1290' with 50 sx cement,

2nd plug at 470' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
(did not) observe this plugging.

DATE 6-2-89

Signed Steve Steinert (TECHNICIAN)

INV. NO. 24949
5-29