

1060154

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,122-0000

 , SEC. 34, T 27 S, R. 21 W/EK

1200 feet from N ~~W~~ section line

1650 feet from ~~N~~W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Young 'F' Well # 1

Operator: TXO Production Corp

County Ford

Name & Address 200 W. Douglas,

Well Total Depth 5050 164.12 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 545

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 10 Month: February Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: PBTD 5023 Perfs 4948 to 4950 4 1/2" set at 5049

1st plug pumped 35 sx cement on bottom 2nd plug 2 sx hulls, 10 sx gel,

50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and dumped an
additional 125 sx cement.

Maximum pressure 600# and shut-in pressure 400#

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:20 pm Day: 10 Month: February Year: 19 84

ACTUAL PLUGGING REPORT PBTD 5023 Perfs 4948 to 4950 4 1/2" set at 5049

1st plug dumped 35 sx cement on bottom through bailer. 2nd plug 2 sx hulls, 10 sx gel,

50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and dumped an

additional 125 sx cement.

Maximum pressure 600# and shut-in pressure 400#

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. They recovered 2720' production pipe. by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-22-84

INV. NO. 03/2

Signed Paul A. Luthi ✓
(TECHNICIAN)