

To: 1 031425  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 057-20,526-0000  
S/2 SE NW, SEC. 34, T 27 S, R 21 W/E  
2970 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4243  
Operator: Cross Bar Petroleum, Inc.  
Name & Address 151 N. Main, Ste. 630  
Wichita, KS 67202-1407

Lease Name T K O Well # 1-34  
County Ford 165.75  
Well Total Depth 5100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 644

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D. S. & W. Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12:01 p.m. Day: 18 Month: 11 Year: 19 96

Plugging proposal received from Kent Strube  
(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 5089' w/120 sx cement, PBTD 5043', Perfs at 4940-44, 4953-57'  
1st plug sand back to 4890' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:59 p.m. Day: 18 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4890' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.

Maximum pressure 450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3560' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE NOV 21 1996  
Observe this plugging.

Signed Steve Durent  
(TECHNICIAN)

DATE NOV 21 1996  
INV. NO. 47011