

Called 8/6/84 Will mail

1 050220

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,377-0000

SE SE SE , SEC. 14 , T 27 S, R. 22 ^{WXX}

330 feet from ~~W~~S section line

330 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Linlor 'A' Well # 2

Operator: Donald C. Slawson

County Ford

Name & Address 200 Douglas Building

Well Total Depth 5165 ^{167.86} feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet ⁴¹⁷

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 17 Month: May Year: 19 84

Plugging proposal received from Ron Rowe

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1440' with 50 sx cement

2nd plug at 900' with 50 sx cement

3rd plug at 450' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Richard W. Lucy
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:30 pm Day: 17 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement, 2nd plug at 900' with 50

sx cement, 3rd plug at 450' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx
cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1984

CONSERVATION DIVISION
Wichita Kansas

INVOICED

DATE 5-25-84

Signed Richard W. Lucy
(TECHNICIAN)

INV. NO. 1677 JUN 04 1984
S-17

JUL 17 1984