

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20-515-A ²⁰²¹⁵⁻⁰⁰⁰¹

NE, SW¹/₄, SEC. 10, T 27 S, R 22 W¹/₄xx

1980 FEET FROM ~~W/S~~ SECTION LINE

1980 FEET FROM W¹/₄ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5021

LEASE NAME RIEGEL WELL # 1-10

OPERATOR: Imperial Oil Company
NAME & 720 Fourth Financial Center
ADDRESS Wichita, KS 67202

COUNTY FORD

WELL TOTAL DEPTH 850 FEET ^{35.00}

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8 FEET 578

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A xx

OTHER WELL AS HEREINAFTER INDICATED OWWO

PLUGGING CONTRACTOR Eagle Drilling LICENSE NUMBER 5380

ADDRESS P.O. Box 8609, Wichita, KS 67208

COMPANY TO PLUG AT: HOUR: 5 am DAY: 22 MONTH: July YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Butch Stinert

(COMPANY NAME) Eagle (PHONE) _____

WERE: Stuck in hole due to lost circulation--did not drill out original plug @ 1099'
to 850--tools lost in hole could not get down below 300feet. Use 60/40 Pozmix, 2%gel
and 3% CaCl and spot a plug at 300 ft w/ 40 sacks and put a top plug at 40 feet to
surface with 10 sx. Circulate 15 sx in rathole and 10 sx in mousehole.

PLUGGING PROPOSAL RECEIVED BY R. B. Bartlett
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE xx

OPERATIONS COMPLETED: HOUR: 7:00 am DAY: 22 MONTH: July YEAR: 19 83

ACTUAL PLUGGING REPORT plugged as proposed.

Cementing by Halliburton.

REMARKS: _____
RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1983
CONSERVATION DIVISION
Wichita, Kansas

I ~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED R. B. Bartlett
(TECHNICIAN)

INVOICED
DATE 8-11-83
INV. NO. 5125-W

FORM CP-2/3
REV. 6-83