

1.050998

1-28-88

187

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,900-0000
C SW/4, SEC. 35, T 27 S, R 20 W/E

R

1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name McFadden D Well # 1

Operator: J. Mark Richardson
Name &
Address 640 Century Plaza Bldg.
Wichita, KS 67202

County Kiowa 158.60

Well Total Depth 4880 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 641

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J. Mark Richardson License Number 5414

Address 640 Century Plaza Bldg., Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 28 Month: 1 Year: 19 88

Plugging proposal received from Carl Schield

(company name) J. Mark Richardson (phone) 316-862-5979

were: 4 1/2" at 4874' PBD 4863' Perfs at 4856-60'

1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:10 p.m. Day: 28 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 03 1988

Maximum pressure 1100 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2440' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)

DATE 2-4-88
INV. NO. 19726