

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20607-00-00
Spot: NW SE Sec/Twnshp/Rge: 35-27S-20W
2130 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: SHERER P Well Number: 1
County: KIOWA Total Vertical Depth: 4909 feet

Operator License No.: 5414 Conductor Pipe: Size _____ feet:
Operator Name: RICHARDSON, J. MARK/RICHARD Surface Casing: Size 8.625 feet: 615
Address: 2843 KEYWEST CT. Production: Size 5.5 feet: 4907 *159.54*
WICHITA, KS 67204 *9/20* Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2000 11:00:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: CARL SCHIELD Company: RICHARDSON, J. MARK/RICHARD Phone: (316) 546-3410

Proposed Plugging Method: AS DIRECTED BY KCC AGENT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/20/2000 10:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS @ 4830-36. SAND TO 4750' WITH 5 SX CMT ON TOP. ON 09/14/00 ALLIED PUMPED 5 SX GEL, 30 SX CMT DOWN 8 5/8". MAXIMUM PRESSURE 50 PSI. BLEW HOLE IN SURFACE PIPE. CIRCULATED APPROXIMATELY 15 SX CMT OUT OF HOLE. ON 09/19/00 DRILLED CMT OUT OF HOLE. ON 09/20/00 RAN TUBING TO 630'. SPOT 50 SX CMT. PULL TO 300' SPOT 40 SX CMT. PULL TO 60' CIRCUALTED 20 SX CMT TO SURFACE. STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 800' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

INVOICED

9/22/00

2001060725

SEP 21 2000

MP

Form *[Signature]*