

To: 1 090313 8-13  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-24,672  
100' SE of  
C NE NE, SEC. 35, T. 27 S, R. 20 W/E  
730 feet from NXX SX section line  
590 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4677

Lease Name Zimmerman Well # 1

Operator: Cara Ventures

County Kiowa

Name & Address: ~~Box 150, RR 2~~ Box 287

Well Total Depth 4882 145.66 feet

Attica, KS-67005 67009

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 653

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 2 p.m. Day: 13 Month: 8 Year: 1993

Plugging proposal received from Paul Caragianis

(company name) Cara Ventures (phone) 316-254-7579

were: 4 1/2" at 4881' w/170 sx cement, Perfs at 4864-78'

1st plug sand back to 4800' and dump 2 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 13 Month: 8 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 2 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2680' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE: AUG 20 1993

Signed [Signature] AUG 18 1993  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 38499

8-13 OCT. 13 1993 MAR 15 1994