

1 090016

8-10

Docket #D-22,383

API NUMBER 15- 097-20,448 -0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C W/2 SE SW, SEC. 26, T 27 S, R 20 W/X

660 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Nelson Well # 2 SWD

Operator: J. Mark Richardson

County Kiowa 158.76

Name & Address 111 West Douglas,
Wichita, KS 67202

Well Total Depth 4885 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 598

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number 5414

Address Box 632, Greensburg, KS 67054

Company to plug at: Hour: 2:30 p.m. Day: 10 Month: 8 Year: 19 89

Plugging proposal received from J. Mark Richardson

(company name) J. Mark Richardson (phone) 316-862-5936

were: 4 1/2" at 4884' Perfs at 4848-60'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 110 sx cement.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 4 p.m. Day: 10 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 110 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2111' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 8-17-89

Signed Michael R Wilson (TECHNICIAN)

INV. NO. 25666

8-10