

1 050835

15-097-00220-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Docket # D-20,054
Drilled 2-26-76
API NUMBER 15-
C NW SE, SEC. 27, T 27 S, R 20 W WEX
1980 feet from S section line
1980 feet from E section line
Lease Name Nelson "D" Well # 1 SWD
County - Kiowa 161.85
Well Total Depth 4980 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 604

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414
Operator: J. Mark Richardson
Name & Address 640 Century Plaza Bldg.
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 632, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 28 Month: July Year: 1986

Plugging proposal received from Bill Folls

(company name) Kelso (phone) (316) 938-2457

were: 4 1/2" at 4968' PBSD N/A Perfs at 4876-4532'

1st plug sanded bottom back to 4470' and dumped 4 sx cement on top of sand through
bailer, 2nd plug 3 sx hulls and 125 sx Econolite with 2 sx hulls mixed in (Pumped
down 8 5/8)

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 28 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 4470' and dumped 4 sx cement

on top of sand through bailer, 2nd plug 3 sx hulls and 125 sx Econolite with 2 sx hulls
hulls mixed in (Pumped down 8 5/8)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

7-31-86
JUL 31 1986

Maximum pressure 350 psi and shut in 150 psi.

Remarks: Recovered 2526' of 4 1/2" casing. Used Econolite; pumped by Halliburton.
(If additional description is necessary, use BACK of this form.)

NOTICED Observe this plugging.

DATE JUL 31 1986

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 14590

7-28

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Nelson "D" #1
 C-NW-SE Sec 27-27-20
 Kiowa County Kansas

Old Information:

Operator: Walters Drilling Co.

Commenced: 4-1-64
 Completed: 4-28-64 TD-4980

New Information:

Operator: J. Mrk Richardson

Commenced: 2-22-76
 Completed: 2-26-76

From	Depth To	Formation	Remarks
0	480	Cement	Ran 504' of 8 5/8" csg
480	543	Cement-Heavy Mud	Cemented 2/300 sks cement
543	4980	Heavy Mud	(was Western Drlg. Co. Nelson "D" #1)
	4980 - TD		Ran 158 jts of New 10 1/2" & 11 1/2" - 4 1/2" csg set @ 4968' Cemented w/ 250 gallon Mud Flush 125 sks 18% Salt Sat Posmix PD @ 11:45 a.m. 2-26-76

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled C-NW-SE Sec 27-27-20, Kiowa County, Kansas to the best of my knowledge and belief.

James S. Sutton II
 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said county and state, on this 25th day of March, 1976, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

