

To: 1 040680
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-4

API NUMBER 15- 151-20,349-0000 26P
SW NE SW, SEC. 17, T. 27 S, R. 12 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers Inc.
Name & Address P.O. Box 251
Great Bend, KS 67530

Lease Name Hoeme Well # 1
County Pratt 89.37
Well Total Depth 2750 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well X Input Well SMD Well D&A
Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:45 a.m. Day: 4 Month: 8 Year: 19 92
Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

were: 4 1/2" at 2745' w/100 sx cement, Perfs at 2678-84'
1st plug sand back to 2628' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, and 100 sx cement,

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 10:30 a.m. Day: 4 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 2628' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 400 psi and shut in 225 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2020.25' of casing.
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1992

INVOICED
I hereby acknowledge and agree to observe this plugging.

DATE 8-20-92
INV. NO. 35994

Signed Steve Pfeifer
(TECHNICIAN)