

1 080238

T8:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SE NW, SEC. 17, T 27 S, R 12 W/8  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,465-0000  
2970 feet from N SE Corner of ~~KXS~~ section line  
3300 feet from W SE Corner of ~~KXE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427  
Operator: D. R. Lauck Oil Co., Inc.  
Name & Address 221 South Broadway, Suite 400  
Wichita, KS 67202

Lease Name Hoeme B Well # 1  
County Pratt  
Well Total Depth 2740 89.05 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 19 Month: October Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 2739' PBD 2707' Perfs 2686-92'

1st plug sand back to 2630' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 19 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 2739' PBD 2707' Perfs 2686-92'

1st plug sanded back to 2630' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,  
released 8 5/8" rubber plug and pumped 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

8-24-84

Maximum pressure 100 psi, shut in at 0 psi. Opened valve - on vacuum.

Remarks: Recovered 2000' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by volume.  
(If additional description is necessary, use BACK of this form.)

(If desired, you may observe this plugging.)

INVOICED

Signed J. H. Metz (TECHNICIAN) SD

DATE 10-29-84

INV. NO. 4510  
10-19