

11-16-87 15-151-21806-0000

To: 1 120047  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 10/14/86

SW NW NE, SEC. 17, T 27 S, R 12 W/E

4290 feet from S section line

2310 feet from E section line

Lease Name Hoeme Well # 1-A

County Pratt 144.76

Well Total Depth 4454 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 259

TECHNICIAN'S PLUGGING REPORT

Operator License # 3181

Operator: W.K. Black PPPLP

Name & Address 1540 North Broadway, Suite 202

Wichita, KS 67214

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 16 Month: 11 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 2794' PBTD 2752' Open hole 2794-4454' Elevation 1967' GL

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper

plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2 p.m. Day: 16 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 50 lbs. hulls and 35 sx

common cement. Shut in with 700 psi at 2500'.

2nd plug pumped into 10 3/4" surface casing with 300 lbs. hulls, 15 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released wiper plug and pumped 150 sx cement

Pumping pressure 200-500 psi. Shut in pressure 100 psi.

NOV 19 1987 11-19-87

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dean Rankin (TECHNICIAN)

DATE 12-3-87

INV. NO. 19080