

To: 1 041273
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-151-22,120-0000
150' S of
E/2 NE NE, SEC. 17, T 27 S, R 12 W/EX
4470 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 31283
Operator: Rheem Resources
Name: _____
Address 100 S. Main, Ste. 505
Wichita, KS 67202

Lease Name Hoeme Well # 1
County Pratt 143.00
Well Total Depth 4400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 366

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:30 p.m. Day: 13 Month: 11 Year: 1997

Plugging proposal received from Ron Schraeder
(company name) Rheem Resources (phone) 316-263-0898

work: 5 1/2" at 4398' w/185 sx cement, PBTD 4366', Perfs at 4146-90'
1st plug pump down 5 1/2" with 50 sx common cement, displace to 3300',
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"
wiper plug and pump 150 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
11-19-97 NOV 19 1997

Plugging Proposal Received by Richard Lacey WICHITA, KS
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3 p.m. Day: 13 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT Junk in hole=bulldog bailer, check valve, 20 jts. 2 7/8" tubing
Top of tubing 3353', probable bottom of bailer at 4003'

11/4/97 Allied ran slick line inside 5 1/2" casing, set down at 2960'.
1st plug pumped down 5 1/2" casing with 50 sx common cement, stopped plug at 2900'. Maximum pressure 400 psi and shut in 350 psi.

11/13/97 2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement. Maximum pressure 200 psi and shut in 65 psi.
Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2150' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I observed this plugging.

DATE 11-24-97
INV. NO. 49580

Signed Stephen J. Pfeifer
(TECHNICIAN)