

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. Mark Richardson

Complete Address 200 O.W. Garvey Bldg., Wichita, Kansas

Lease Name Nettie Dean Well No. 2

Location C NW NW Sec. 11 Twp. 27 Rge. 22 ~~(E)~~ (W)

County ~~XX~~ Ford Total Depth 5020'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Pratt Well Service

Address Pratt, Kansas License No.

Operation Completed: Hour 4:00 P^M Day 19 Month 7 Year 1974

The above well was plugged as follows:

8 5/8" to 536' circulated w/ cement. ~~XXX~~ 4 1/2" to 5020' cemented.

Top perforations 4947' Plug bottom w/ 35 sacks cement.

Top of cement 4450' Mud 4450' to 400'

Bridge & 4 Yards Ready Mix Concrete 400' to 0'.

Pulled 2530' of 4 1/2" casing.

INVOICED I hereby certify that the above well was plugged as herein stated.

DATE 7/23/74

INV. NO. 9568-w

Signed: Edgar J. Beer
Well Plugging Supervisor