

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frank J. Blsck

Complete Address Box 150 McPherson, KS

Lease Name Zimmerman Well No. D-2

Location C NE/NE Sec. 35 Twp. 27 Rge. 20 (E) (W)

County Kiowa Total Depth 4974

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 3:00 PM Day 12 Month 11 Year 1974

The above well was plugged as follows:

355 ft 8 5/8 surface cemented with 225 sacks. 4969 ft 5 1/2 long string
cemented with 100 sacks. Open hole. Sand to 4600 ft, 5 sacks cement
with bailer. Pulled 2700 ft 5 1/2. Pump 2 sacks hulls, 10 gel, 100 sacks
cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

DATE 11/14/74
INV. NO. 295-W

Signed: [Signature]
Well Plugging Supervisor