

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Co. Inc.

Complete Address Box 169 Russell, Ks 67665

Lease Name Hoeme Well No. 4

Location NE/SW/SW Sec. 17 Twp. 27 Rge. 12 (E) (w)W

County Pratt Total Depth 4420

Abandoned Oil Well        Gas Well        Input Well X SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 7:00 PM Day 9 Month 7 Year 1970

The above well was plugged as follows:

326 ft of 8 5/8 surface pipe cemented with 330 sacks. 4419 ft of 5 1/2  
long string cemented with 150 sacks. Set plug at 3700. Sand back  
to 3670, 5 sacks cement with bailer. Pulled 3289 ft of 5 1/2. Fill hole  
to 320 ft, 10 ft rock bridge, 25 sacks cement. Mud to 40 ft, 10 ft  
rock bridge. 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/13/70  
INV. NO. 2207-u

Signed: [Signature]  
Well Plugging Supervisor