

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Co. Inc.

Complete Address Box 169 Russell, Ks 67665

Lease Name Hoeme Well No. 3

Location G S/2 NW/SW Sec. 17 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4444

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 7:30 PM Day 30 Month 6 Year 1970

The above well was plugged as follows:

320 ft of 8 5/8 surface pipe cemented with 225 sacks. 4444 ft of  
5 1/2 long string cemented with 250 sacks. Set plug at 3720 ft., sand  
back to 3690, 5 sacks cement with bailer. Pulled 2907 ft of 5 1/2, 10  
ft rock bridge, 320 ft., 25 sacks cement, 10 ft rock bridge, 40 ft,  
10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. Russell Schubert  
Well Plugging Supervisor

DATE 7/2/70  
INV. NO. 2155-W