

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address Box 169 Russell, Ks 67665

Lease Name Hoeme Well No. 1

Location NE/NW/SW Sec. 17 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4465

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 7:30 PM Day 27 Month 6 Year 1970

The above well was plugged as follows:

315 ft of 8 5/8 surface pipe circulated. 4450 ft of 5 1/2 long string
cemented with 200 sacks. Set plug at 3700 ft. Sand to 3670 ft,
5 sacks cement with bailer. Pulled 3117 ft of 5 1/2. Set 10 ft. rock
bridge at 300 ft., 25 sacks cement. Mud to 40 ft, 10 ft rock bridge,
10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/30/70
INV. NO. 2127-4

Signed: [Signature]
Well Plugging Supervisor