


KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address Box 169 Russell, Ks 67665

Lease Name Hoeme C Well No. 1

Location SW/SW/NW Sec. 17 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4501

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lynch Casing Pulling Co.

Address RT 4 Great Bend, Ks License No. 457

Operation Completed: Hour 6:30 PM Day 21 Month 7 Year 1970

The above well was plugged as follows:

264 ft of 8 5/8 surface pipe circulated. 4499 ft of 5 1/2 long string
cemented with 125 sacks. Top plug at 3750. Sand back to 3700, 10
sacks cement with bailer. Pulled 2507 ft of 5 1/2. 10 ft rock bridge,
at 260 ft, 25 sacks cement. Mud to 40 ft, 10 ft rock bridge, 10 sacks
cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/24/70
INV. NO. 2274-u

Signed: [Signature]
Well Plugging Supervisor