

KANSAS

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address Box 169 Russell, Ks 67665

Lease Name Home C Well No. 2

Location NE/SW/NW Sec. 17 Twp. 27 Rge. 12 (E) (W)

County Pratt Total Depth 4424

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 4:00PM Day 22 Month 7 Year 1970

The above well was plugged as follows:

264 ft of 8 5/8 surface pipe circulated. 4423 ft of 5 1/2 long string
cemented with 125 sacks. Plug at 3730 ft. Sand back to 3690 ft, 5
sacks cement with bailer. Pulled 2013 ft of 5 1/2. Set 10 ft rock
bridge at 250 ft, 25 sacks cement. Mud to 40 ft, 10 ft rock bridge,
10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/24/70
INV. NO. 2275-14

Signed: *Russell Biherton*
Well Plugging Supervisor