

15-151-10163-0000
Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued June 23, 1967.

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name Helmke "J" Well No. # 6

Location SW NE SE Sec. 6 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4277'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stfford, Kansas License No. 490

Operation Completed: Hour 9:30AM Day 3rd Month Oct. Year 1967

The Above well was plugged as follows:

460' of 8 5/8" surface pipe, cemented with 250 sacks. 4277' of 4 1/2" long string,
cemented with 250 sacks. Plug back T.D. 4212'. Top perferation 4085'. Bottom of
the hole was sanded to 4025', and cemented with 20 sacks, through the dump bailer,
with cement from 4025' to 3865'. 3023' of 4 1/2" long string was recovered from the
hole. Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from
300' to 290'. 6 sacks of cement was mixed in a barrel, and put on plug at 290',
through the dump bailer, and let set over-night. Next day hole was bailed dry, and
19 sacks of cement was added to the plug, with cement from 290' to 215'. Hole was
filled with mud to 40', rock Bridge from 40' to 30', and cemented with 10 sacks,
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/4/67

INV. NO. 6451-W