

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued June 23, 1967.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name Helmke "H" Well No. # 1

Location C NE NE NE Sec. 6 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4326'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 9:30AM Day 9th Month October Year 1967

The Above well was plugged as follows:

443' of 8 5/8" surface pipe, cemented with 225 sacks. 4209' of 5 1/2" long string, cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded to 4150', and cemented with 20 sacks, with cement from 4150' to 3990'. 2309' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from 300' to 290'. 6 sacks of cement was mixed in a barrel, and put on plug at 290', through the dump bailer, and let set over week-end. Hole was bailed dry, and 19 sacks of cement was added to the plug, with cement from 290' to 215'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Aubie Elving  
Well Plugging Supervisor

INVOICED

DATE 10/11/67

INV. NO. 6482-11