

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Cunningham "B" Well No. # 6

Location SW SE SW Sec. 19 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3479'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:30PM Day 28th Month Sept. Year 1966

The Above well was plugged as follows:

323' of 12 1/2" surface pipe, cemented with 275 sacks. 3400' of 7" long string,
cemented with 500 sacks. This is an open hole. Bottom of the hole was sanded
to 3380', and cemented with 25 sacks, through the dump bailer. 2500' of 7"
long string was recovered from the hole. Bridge plug was pushed in fluid to
320', rock bridge from 320' to 310'. 10 sacks of cement was mixed in a barrel
and put on plug at 310', through the dump bailer, and let set over-night. Next
day hole was bailed dry, and 25 sacks of cement was added to the plug. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented with
15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 10/3/66
INV. NO. 4040-W