

15-095-00674-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Wendel Leisman Well No. # 7

Location App. C NW Sec. 20 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 4222

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 12:00PM Day 20th Month June Year 1964

The Above well was plugged as follows:

363' of 8 5/8" surface pipe, cemented with 200 sacks. 4221' of 4 1/2" long
string, cemented with 500 sacks. Plug back to 3483'. Top perforation
3382'. Bottom of the hole was sanded to 3360', and cemented with 3 sacks.
Hole was filled with mud to 275', with 10' of rock bridge, and cemented
with 25 sacks. Hole was filled with mud to 40', with 10' of rock bridge,
and cemented with 10 sacks to base of the cellar.
1820' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/23/64
INV. NO. 9357-W