

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Richardson of Richardson has this

date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: J. Mark Richardson

Complete Address: 200 O.w. Garvey Bldg., Wichita, Kansas

Lease Name: Nettie Well No. 2

Location: G NW NW Sec. 11 Twp. 27 Rge. 22 XX
(E) (W)

County: Ford Total Depth 5020' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:


8 5/8" to 536' cirul ted w/ cement. 4 12" to 5020' cemented.

Top perforaions 4947' Plug bottom w/35 sacks cement.

Top of cement 4450' Mud 4450' to 400'

Bridge & 4 Yards Ready Mix 400' to 0'.

Very truly yours,


Conservation Division Agent