

15-55-20549-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Reno SEC. 23 TWP. 26S RGE. 9W E/W
 Location as in quarters or footage from lines:
C NE/4 NW/4

Lease Owner George R. Shaw
 Lease Name Edna Brown 2-A Well No. _____
 Office Address 1001 Union Center Bldg. Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 5-13-82
 Plugging completed 7-20-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
 Producing formation _____ Depth to top _____ bottom T.D. 2779'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	264'	none
				5-1/2"	2779'	1212'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 1450' and ran 5 sacks cement. Shot casing @1332', and 1210' and pulled a total of 29 joints of 5-1/2" casing. Plugged surface with 3 sacks hulls, 25 sacks gel, 8-5/8" plug, 100 sacks 50/50 pos, 4% gel, 3% cc.
Plugging Complete.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

7-22-82



(Signature) [Signature]
 Box 347 Chase, Kansas 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 82



[Signature]
 Notary Public.

My Commission expires:



A Division of Halliburton Company
DUNCAN, OKLAHOMA 73536

BULK MATERIALS DELIVERY AND TICKET CONTINUATION

FOR INVOICE AND
TICKET NO.

15-155-20544-0000

DATE 7-20-82	CUSTOMER ORDER NO.	WELL NO. AND FARM <i>Edna Brown 2-17</i>	COUNTY Reno	STATE Ks.
CHARGE TO George R. Shaw		OWNER Sane	CONTRACTOR No. B 232414	
MAILING ADDRESS <i>1001 Union Center Bldg-</i>		DELIVERED FROM Great Bend, Ks.	LOCATION CODE 50320	PREPARED BY J.V. Osborn
CITY & STATE <i>Wichita, Kansas 67202</i>		DELIVERED TO Location	TRUCK NO. <i>9066-6604</i>	RECEIVED BY

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE			DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT
		L	D	o		QTY.	MEAS.	QTY.	MEAS.		
					100 Pozmix Cement 2% Gel						
504-043		2	b		Regular Portland	50	sk			5.25	262.50
506-105		2	b		Pozmix A	50	cuft			2.46	123.00
506-121		2	b		2 Halliburton Gel 2% Allowed						NC
509-554		2	b		25 Halliburton Gel	25	sk			6.30	157.50
509-406		2	b		Calcium Chloride 3% W/100	3	sk			21.00	63.00
<div style="position: absolute; transform: rotate(-45deg); opacity: 0.5; font-size: 2em; font-weight: bold;">THIS IS NOT AN INVOICE</div>											
<div style="position: absolute; transform: rotate(45deg); opacity: 0.5; font-size: 1.5em; font-weight: bold;">RECEIVED STATE CORPORATION COMMISSION AUG 09 1982 CONSERVATION DIVISION Wichita, Kansas</div>											
					Returned Mileage Charge						
					TOTAL WEIGHT		LOADED MILES		TON MILES		
					SERVICE CHARGE ON MATERIALS RETURNED				CU. FEET		
500-207		2	b		SERVICE CHARGE				CU. FEET	106	.95
500-306		2	b		Mileage Charge	11,308	62		TON MILES	350.55	.70
					TOTAL WEIGHT		LOADED MILES		TON MILES		
No. B 232414		CARRY FORWARD TO INVOICE						SUB-TOTAL		952.08	

CUSTOMER

15-55-20549-0000

Geo. R. Shaw
1001 Union Center Bldg.
Wichita, Kansas 67202

Brown #2-A
C NE NW Sec. 23-26S-9W
Reno County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: December 12, 1978
Completed: December 18, 1978

Drillers Log

Sand	120
Red Bed	800
Shale	1232
Anhydrite	1242
Shale & Salt	1480
Shale & Shells	2224
Shale & Lime	2326
Shale & Shells	2680
Lime & Shale	2760
Lime	2785 RTD

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1979
CONSERVATION DIVISION
Wichita, Kansas