


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 23 Twp. 26 Rge. 9 (E) (W) x
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Sierra Petroleum Co.
Lease Name Eluke Well No. #1
Office Address 211 North Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 8-1-66 19
Application for plugging approved 19
Plugging commenced 8-3-66 19
Plugging completed 8-5-66 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3265' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 2225', mixed and ran 3 sacks cement thru dump bailer.
Mudded hole to 225', set 10' rock bridge. Mixed and ran 30 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec
Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1966

My commission expires 24 October 1968
Sidney D. Miller Notary Public.

NO. 1 FLUKE

15-155-3045-0000

Well Record:

Location: Ctr. NE/4 SW/4
Section 23-26S-9W
Reno County, Kansas

Commenced: May 6, 1966

Completed: May 14, 1966
(Rotary)

Contractor: Messman-Rinehart Oil Company
1432 Wichita Plaza
Wichita, Kansas, 67202

Elevation: 1678' K/B

Operator: Sierra Petroleum Co., Inc.
211 N. Broadway
Wichita, Kansas, 67202

Production: Gas

Casing Record: 8-5/8" @ 227' w/225 sx. cement, 2% gel
4-1/2" @ 2480' w/125 sx. cement

*** LOG ***

(Figures indicate bottom of formation)

Clay and Sand	150
Red Bed & Shale	225
Shale & Shells	300
Shale & Red Bed	1195
Anhydrite	1235
Salt & Shale	1305
Shale & Shells	1350
Shale & Shells - Lime	1455
Lime	2210
Shale & Sand	2240
Sand & Shale	2442
Lime & Shale	2540
Shale & Lime	2690
Shale	2810
Shale & Lime	2985
Lime & Shale	3115
Shale	3192
Lime & Sand	3260
Lime	3265 R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1966
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this
27th day of May, 1966

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1968

6-2-66
Copy to Baker