

*Reece Jones*

15-155-30/47-0000

Form CP-4


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Reno County, Sec. 24 Twp. 26 Rge. 9 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW/4  
Lease Owner Robert F. White  
Lease Name Reece Jones #1x Small #1 Reece-Jon Well No. 1  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 2/10/71 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 2/15/71 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2412 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	298	none
				5 1/2"	2412'	1565'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 2300', ran sand to 2200' and ran 3 sacks of cement.  
Loaded hole with water, shot pipe at 1957', 1860', 1763', 1664', 1567',  
worked pipe loose and pulled 49 joints. Bailed hole to 225', set 10'  
rock bridge and ran 25 sacks of cement. Mudded to 40', 10' rock bridge  
and ran 10 sacks of cement on top. Tallied pipe.

PLUGGING COMPLETE.


RECEIVED  
STATE CORPORATION COMMISSION  
MAR 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*  
CHASE, KANSAS (Address)

Subscribed and Sworn to before me this 18th day of February, 19 71



*Margaret Melcher*  
Notary Public.

My commission expires 2/15/75

NO. 1 REECE-JONES UNIT

15-155-30147-0000

Well Record:

Location: App. Ctr. N/2 S/2 NW/4  
 Section 24-26S-9W  
 Reno County, Kansas

Commenced: June 7, 1966

Completed: June 15, 1966  
 (Rotary)

Contractor: Messman-Rinehart Oil Company  
 1432 Wichita Plaza  
 Wichita, Kansas

Elevation: 1677' K/B

Operator: Robert F. White  
 714 Union Center Bldg.  
 Wichita, Kansas, 67202

Casing Record: 8-5/8" @ 221' w/215 sx. cement  
 4-1/2" @ 2485' w/120 sx. cement

\*\*\* L O G \*\*\*

(Figures indicate bottom of formation)

Sand	85
Red Bed & Shells	221
Shale & Red Bed	445
Red Bed	700
Shale & Shells	1205
Anhydrite	1255
Salt & Shale	1327
Shale & Shells	1420
Lime	1760
Lime & Shale	2165
Shale & Sand	2240
Sand & Shale	2395
Lime & Shale	2790 R.T.D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 26 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland  
 J. A. Gilliland

Subscribed and sworn to before me this  
 20th day of June, 1966

B. J. Scott  
 Barbara J. Scott, Notary Public

Commission Expires: December 1, 1968

