


Give All Information Completely
Make Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 29 Twp. 26S Rge. (E) 9 (W)
Location as "NE/CNWSWK" or footage from lines SE SE NE
Lease Owner Natural Gas and Oil Company
Lease Name Foster Well No. 1
Office Address P. O. Box 105, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-4-58 19
Application for plugging filed 9-5-58 19
Application for plugging approved 9-5-58 19
Plugging commenced 9-5-58 19
Plugging completed 9-5-58 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampell
Producing formation Depth to top Bottom Total Depth of Well 4005 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	279	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 260 feet
Plug, 1/4 sack hulls, 20 sacks cement
Mud to 35 feet
Plug, 1/4 sack hulls, 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones Drilling Company, Inc.
Address 511 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. B. Steele, Jr. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,

(Signature) J. B. Steele, Jr.
P. O. Box 105, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 1958

Richard R. Beach

My commission expires July 27, 1959

Notary Public.

PLUGGING
FILE SEC 29 T 26 R 9W
BOOK PAGE 128 LINE 24

15-155-39350-0000

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

FOSTER #1
SE SE NE SECTION 29-26S-9W
RENO COUNTY, KANSAS

COMMENCED 8-26-58
COMPLETED 9-5-58

FROM	TO	FORMATION	REMARKS
0	40	SHALE	
40	120	CLAY & SAND	
120	150	GRAVEL	
150	279	RED BED & SHALE	RAN 282.19' OF 8 5/8" CASING, CEMENTED @ 279" WITH 225 SACS CEMENT.
279	980	RED BED SHALE & SHELLS	
980	1249	SHALE	
1249	1270	LIME	
1270	2350	LIME & SHALE	
2350	2535	SHALE & SHELLS	
2535	2850	SHALE & LIME	
2850	2925	SANDY LIME	
2925	3475	LIME & SHALE	
3475	3745	LIME	
3745	3890	LIME & SHALE	
3890	3960	LIME	
3960	4005	LIME & CHERT	
4005	TD		DRY & ABANDONED

I, E. E. HALL, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE
DRILLER'S WELL LOG FOR THE FOSTER #1.

E. E. Hall

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID
COUNTY AND STATE, ON THIS 12TH DAY OF SEPTEMBER, 1958 PERSONALLY
APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON
WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME
THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE
USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL
THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES Sept. 3, 1962

Catherine L. Luce
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1958
PLUGGING
FILE SEC 29 T 26 R 9W
BOOK PAGE 128 LINE 24
CONSTRUCTION DIVISION
Wichita, Kansas

SEP 13 1958