

15-155-20574-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County. Sec. 31 Twp. 26S Rge. 9 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW NE SE

Lease Owner Martin & Visa Exploration  
Lease Name Claypool Well No. 1  
Office Address P.O. Box 36078, Denver, CO 80236  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed 2-15 1979  
Application for plugging filed 3-2 1979  
Application for plugging approved 3-9 1979  
Plugging commenced 3-2 1979  
Plugging completed 3-5 1979  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4232  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surface	321'	8 5/8"	321'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bridged to 1550; 3 sacks cement thru bailer;  
Lay down 1417' 4 $\frac{1}{2}$  casing put top plug @ 310' to 300 with rock; 25 sacks cement; fluid to 50'; 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1979

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this report)  
Name of Plugging Contractor Catlett Drilling Company

STATE OF Colorado COUNTY OF Denver, ss.  
M.J. Wohnlich (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
PIONEER DRILLING CORPORATION  
P.O. Box 36078, Denver, CO 80236  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of March, 1979

[Signature]  
Notary Public.

My commission expires July 1, 1980

DRILLERS LOG

Martin & Visa Exploration  
Claypool #1  
NW NE SE, Sec. 31-T26S-R9W  
Reno County, Kansas

Elev. - 1734 K.B..  
Surface Casing: 321' of  
8 5/8"

15-155-20574-0000

Commenced: 1-29-79  
Completed: 2-15-79

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	321
Shale	321 - 448
Shale	448 - 1060
Shale	1060 - 1241
Shale & Lime	1241 - 1455
Shale & Lime	1455 - 1610
Shale - Lime	1610 - 1622
Shale - Lime	1622 - 1835
Shale - Lime	1835 - 2046
Shale & Lime	2046 - 2139
Shale & Lime	2139 - 2219
Shale - Sand	2219 - 2382
Shale - Sand	2382 - 2524
Lime & Shale	2524 - 2668
Shale - Lime	2668 - 2820
Shale - Lime	2820 - 2962
Lime & Shale	2962 - 3029
Shale & Lime	3029 - 3176
Shale - Lime	3176 - 3308
Lime & Shale	3308 - 3340
Lime - Shale	3340 - 3345
Lime & Shale	3345 - 3412
K.C.	3412 - 3525
K.C. - Lime	3525 - 3742
Lime & Shale	3742 - 3908
Lime & Shale	3908 - 3935
Miss. - Chat.	3935 - 3960
Miss. - Chat.	3960 - 3970
Mississippi	3970 - 4022
Mississippi	4022 - 4145
Shale & Lime	4145 - 4223
Viola	4223 - 4232 RTD

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 19 1979  
CONSERVATION DIVISION  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

PIONEER DRILLING CORPORATION

*[Handwritten Signature]*

State of Colorado )  
                          ) ss.  
County of Denver )

Subscribed and sworn to before me this 23rd day of February, 1979.

My Commission Expires: July 1, 1980

*[Handwritten Signature]*  
Notary Public