


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 32 Twp. 26 Rge. (E) 9 (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Edwin G. Bradley  
Lease Name Foster "A" Well No. 1  
Office Address 826 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) gas  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed March 28 1966  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced March 30 1966  
Plugging completed April 1 1966  
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3998 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	314'	8 5/8"	314'	none
		0	3995'	5 1/2"	3995'	3143.00

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 3930', set 10' rock bridge and dumped 5 sacks of cement.

Pushed plug to 300'. Set 10' rock bridge and dumped 25 sacks of cement. Filled hole with mud to 40', set 10' rock bridge and capped hole with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1966  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells

Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1966

My commission expires July 7, 1968

J. Rader  
Notary Public.

WELL LOG

15-155-02383-600

Well: Foster #A-1  
 Location: C SE/4 NW/4  
 Section 32-26-9  
 Reno County, Kansas  
 Operator: Edwin G. Bradley  
 Union Center Building  
 Wichita, Kansas  
 Casing: 8-5/8" 314' w/175 Saz  
 5-1/2" 3998' w/125 Saz

Contractor: Twin Drilling, Inc.  
 1005 Central Building  
 Wichita, Kansas  
 Commenced: 10-17-58  
 Completed: 10-26-58

Surface 25  
 Sand 205  
 Shale-Shells 1350  
 Shale W/Lime Streaks 1618  
 Lime 1945  
 Shale & Lime 2590  
 Lime 2655  
 Shale & Lime 3112  
 Lime 3237  
 Lime & Shale 3400  
 Lime 3942  
 Miss. Lime 3961  
 Lime 3995

Tops

Heebner 3240'  
 Br. Lime 3402'  
 Lansing 3434'  
 Miss. 3942'

T.D. 3995'

RECEIVED  
 STATE DEPARTMENT OF COMMISSIONS

MAY 3 - 1966

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF SEDGWICK )

The undersigned, TWIN DRILLING, INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

TWIN DRILLING, INC.

By Alvada Day

Subscribed and sworn to before me  
 this 15th day of November, 1958.

James A. Nickle  
 Notary Public

My commission expires  
 September 29, 1960.