

15-155-60246-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Reno County, Sec. 32 Twp. 26 Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Murfin Drilling Co.

Lease Name L. D. Foster Well No. 1

Office Address 507 Union Nat. Bank Bldg - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 7-27 19 55

Application for plugging filed 7-27 19 55

Application for plugging approved 7-27 19 55

Plugging commenced 7-27 19 55

Plugging completed 7-27 19 55

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 4406 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	285	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filed hole with mud laden fluid.  
Set 1st plug, displaced 15 sacks of cement through drill pipe.  
Filled hole to 20'.  
Set 2nd plug, displaced 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Co.

Address 507 Union Nat Bank Bldg - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Murfin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W R Murfin*

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 55.

My commission expires 6-13-59.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1955  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 32 T 26 R 9W  
BOOK PAGE 138 LINE 13

# WELL LOG

15-155-60246-0000

COMPANY **Murfin Drilling Company**

SEC. **32** T. **26** R. **9W**

FARM **L. D. Foster** NO. **1**

LOC. **SW SW NE**

TOTAL DEPTH **4406**

COUNTY **Reno**


COMM. **7-5-55**

COMP. **7-27-55**

KANSAS

SHOT OR TREATED

CONTRACTOR **Murfin Drlg. Co.**



ISSUED

### CASING

20	10
15	8 .285" w/200 SX.
12	6
13	5

ELEVATION **1730 DF**

**1732 RB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

110	Shale
210	Sand
400	Red Bed
880	Shale & Shells
1255	Shale
1310	Lime & Shale
1385	Lime
1435	Salt & Shale
1550	Shale - Lime & Shells
1575	Shale & Shells
1765	Lime & Shale
1790	Lime
1800	Red Bed
1990	Lime & Shale
2165	Lime - Sand & Shale
2535	Shale & Lime
2560	Shale
2595	Lime - sandy
3450	Shale & Lime
3525	Lime
3570	Lime & Shale
3930	Lime
4000	Lime - cherty
4125	Lime & Shale
4160	Shale
4205	Shale - Lime
4214	Lime
4220	Lime (Viola)
4300	Lime
4330	Lime & Sand
4400	Shale & Lime
4406	Lime

### Tops:

Heebner	3236
Douglas sand	3285
Brown Lime	3401
Lansing - KC	3412
BKC	3740
Miss. Chat	3943
Kinderhook	4024
Viola	4205
Simpson Shale	4292
Simpson sand	4297
Arbuckle	4385
RTD	4406

4406 TD  
 State of Kansas  
 County of Sedgwick

**PLUGGING**  
 FILE SEC 32 T. 26 R. 9W  
 BOOK PAGE 38 LINE 13

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG 11 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the L. D. Foster #1 well.

Subscribed and sworn to before me this 3rd day of August 1955.

My Commission Expires: 6-13-59

W. R. Murfin  
 \_\_\_\_\_  
 Betty Spragg  
 NOTARY PUBLIC