

API NUMBER 15-155-21,141-000

LEASE NAME Compton

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

1320 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 2 TWP. 26 RGE. 10 (W)

COUNTY Reno

Date Well Completed 08-08-90

Plugging Commenced 08-08-90

Plugging Completed 08-08-90

LEASE OPERATOR Molitor Oil, Inc.

ADDRESS RR 1 Box 74 Spivey, KS 67142

PHONE# (316) 243-6773 OPERATORS LICENSE NO. 3067

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08-08-90 (date)

by Mr. Tittle (KCC District Agent's Name).

to be filed

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @ 1450' w/35 sacks cement thru drill pipe  
 Next Plug: @ 1000' w/35 " " " " " 15 sacks in Rat Hole  
 Next Plug: @ 230' w/30 " " " " " 10 sacks in Mouse Hole  
 Top Plug: @ 60' w/25 " " " " " water well filled w/cement  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

John Armbruster (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Armbruster

(Address) P.O. Box 823 Great Bend, KS 67530



SWORN TO before me this 20th day of August, 19 90

Sally R. Byers  
 Notary Public

My Commission Expires: DECEMBER 6, 1992

8-21-90

DRILLER'S WELL LOG

15-155-2141-0066

DATE COMMENCED: August 3, 1990  
DATE COMPLETED: August 8, 1990

Molitor Oil, Inc.  
COMPTON #1  
C W/2 W/2 SE  
Sec. 2, T26S, R10W  
Reno County, Ks.

0 - 1740' Surface Soil, Shale, Lime  
1740 - 2756' Lime & Shale  
2756 - 3682' Shale & Lime  
3682 - 3950' Lime  
3950' RTD

ELEVATION: 1719 K.B.

Surface Pipe: Set  
new 8-5/8", 20# pipe @ 184'  
w/120 sacks 60/40 pozmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

John Ambruster of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*John Ambruster*

Subscribed and sworn to before me this 20th day of August 1990.

 SALLY R. BYERS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appl. Exp. 12/10/92

*Sally R. Byers*  
Notary Public

STATE OF KANSAS  
DEPARTMENT OF REVENUE  
DIVISION OF TAXATION

CONSERVATION DIVISION  
Wichita, Kansas