

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Reno County, Sec. 3 Twp. 26 Rge. (E) 10 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE 1/4

Lease Owner M. B. Armer

Lease Name Geesling Well No. 1

Office Address 710 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed May 15 19 52

Application for plugging filed May 15 19 52

Application for plugging approved May 15 19 52

Plugging commenced May 15 19 52

Plugging completed May 15 19 52

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 4440 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	295	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to 270 ft. - spotted
15 sacks cement at 270 ft. Filled with mud and
5 sacks cement at top of surface pipe.

RECEIVED
STATE CORPORATION COMMISSION

5-20-52

MAY 20 1952

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer

Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature)

L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 52

Hayden Walton

Notary Public.

My commission expires Sept. 17, 1955

PLUGGING
FILE SEC-3 T-26 R-100
BOOK PAGE-16 LINE-30

L O G

15-155-00328-0000

Company: M. B. Armer
Contractor: M. B. Armer (Ideco)
Drilling Commenced: 4/27/52
Drilling Completed: 5/15/52
Elevation: 1733 R. D.
1730 D. P.
1727 Gr.

Farm: Geasling #1
Location: SE 34 38 39 Sec. 3-268-107
Reno County, Kansas
Casing Record: 8-5/8" casing at 295' with
175 sacks cement.

(figures below indicate bottoms)

Sand	155
Redbed & shells	365
Redbed & shale	913
Shale, shells & salt	1375
Shale, shells & sand	1630
Shale, shells & sand redbed	1730
Shale & lime	2050
Shale & shells	2175
Shale & lime	2490
Lime, shale & gypsum	2610
Shale & lime	2830
Lime, shale, sand & gypsum	2990
Shale & lime	3340
Shale, shells	3460
Shale & lime	3575
Lime	3720
Lime, broken	3765
Lime	3820
Shale & lime	3952
Lime	3970
Lime & chert	4010
Chert	4015
Shale & lime	4070
Shale	4160
Shale & lime	4230
Lime	4285
Lime & shale	4313
Shale & sand	4370
Lime, shale & sand	4400
Lime	4410
R. T. D.	4440 D. & A.

FORMATION TOPS (R. D. Meas.)

Neohner	3275
Brown lime	3449
Lansing - Kansas City	3467
Mississippi	3940
Viola	4204
Simpson	4295
Arbuckle	4387

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

BY C. P. Sperry

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1952

STATE OF KANSAS)
COUNTY OF SEWICK) CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 14th day of May, 1952.

PLUGGING
FILE SSC-3-T-26-R-102
BOOK PAGE 16 LINE 30

Noel Walton
Notary Public

My Commission expires Sept. 17, 1955.