

LEASE NAME Deterding

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Iannitti Oil Company

SEC. 10 TWP. 26 SRGE. 10W (E) or (W)

ADDRESS P. O. Box 308 Great Bend, KS 67530

COUNTY Reno

PHONE# (316) 792-2921 OPERATORS LICENSE NO. 30395

Date Well Completed

Character of Well oil

Plugging Commenced 2-11-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-14-97

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACQ-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	212'	none
				5 1/2	4043'	2340'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3860' & ran 5 sks cement. Shot at 3028', worked pipe. Shot at 2800', worked pipe. Shot at 2707', worked pipe. Shot at 2612', worked pipe. Shot pipe loose at 2340'. Pulled to 1500', pumped 35 sks w/100# hulls. Pulled to 950', pumped 35 sks w/100# hulls. Pulled to 300' & circulated cement to surface with 100 sks. Plugging complete. 60/40 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, 53.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1997

James Stephens
Notary Public

My Commission Expires:



Rec'd
3-5-97