

15-155-39381-0000

Received,  
6-14-35

# WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission,  
800 Bittling Building,  
Wichita, Kansas.

## FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Reno County. Sec. 27 Twp. 26 Rge. (E) 10 (W)

NORTH



Locate well correctly on above  
640 A. Plat

Lease Name Crotts  
Lease Owner W. E. Witt et al  
Office Address Union National Bank Bldg., Wichita, Kans.  
Character of Well (Oil, Gas or Dry) dry Total Depth of Well 4,430 Feet  
Date, well, completed May 18th 1935  
Application for plugging and log of well filed May 18th 1935  
Application for plugging approved May 21 1935  
Plugging Commenced May 24th 1935  
Plugging Completed                      1935  
Reason for abandonment of well or producing formation                     

If a producing well is abandoned, date of last production                      1935

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Officer who supervised plugging of this well Mr. Theo Morgan  
Producing formation                      Depth to top                      Bottom                     

Show depth and thickness of all water, oil and gas formations.

### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	BW Content	212	220	Size	Put In	Pulled Out
Sand	15 BW	1855	1865			
Sand	H. F. W.	2395	2422			
Sand	3 BW	2795	2835			
Sand	H. F. W.	2843	2863	20"	97	none
Sandy Lime	H. F. W.	3095	3100	15 1/2"	530	530
Kansas City Lime	show of oil	3485	3868	12 1/2"	1239	1170
Dherb & Miss. lime	show of oil	3978	4050	10"	2146	2146
Viola lime	dry	4174	4198	8-5/8 OD	3485	3485
Wilcox sand	water	4338	4375	7" OD	3979	3979
Siliceous lime	water	4425	4430	5-3/16	4367	4278

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from                      feet to                      feet for each plug set.

The mud was put in the hole with a mud-hog pump. The hole was filled with mud as each string of pipe was started and pulled. There was no cement or wooden plugs used in plugging.

(Note to Mr. Theo Morgan--This was a divided contract and our responsibility ended with the pulling of the 8" casing and the above information pertains only to the work done by us. R. E. Garden & Son.)

The above process was carried out on each string of pipe pulled.

This hole was bridged and cemented from 115' to bottom of 20". 20" pipe left in hole.

**PLUGGING**  
FILE SEC 27 T 26 R 10 W  
BOOK PAGE 3 LINE 42

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? yes

Was exception made?                      If so describe                     

Correspondence regarding this well should be addressed to W. E. Witt  
Address Union National Bank Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Reno, SS. contractor

A. L. Privett of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Privett

(Address)

Subscribed AND SWORN to before me this 6th day of June 1935

My commission expires March 29, 1937.

[Signature]  
Notary Public.

RECEIVED  
JUN 14 1935  
BY

CASING RECORD -- 97 FEET 20 INCH

WELL #1  
Lease - Grotts  
Location NE-NW of NE, Sec. 27, Tp 26  
R. 10W, Reno County, Kansas  
Well commenced Sept. 10, 1934  
Well completed May 18, 1935  
Kind of well - Dry  
Total depth 4420.ft.  
COMPANY OPERATING - W.E. Witt and etal.  
CONTRACTORS - A.L. PRIVETT and R.E. GARDEN & SON.

PLUGGED  
FILE SEC 27 T 76 R 10W  
BOOK PAGE 3 LINE 42

530	"	15 1/2"
1230	"	12 1/2"
2146	"	10"
3485	"	8 1/2"
3979	"	65/8"
4367	"	53/16"

	from	to		from	to		from	to
Sand	0	30	Red Rk	1995	2024	Sandy Lime	3365	3376
Clay	30	35	Lime	2024	2034	Sand	3376	3390
Qk Sand	35	51	Bl. Sla.	2034	2050	Sm Show gas	3365-76-1000 Ft	
Red Rock	51	78	Lime	2050	2080	water in four hours	3376-90	
Red Shale	78	92	Bl. Sla.	2080	2100	1600 Ft water at	3400 ft.	
Red Rock	92	212	Lime	2100	2105	Sand HFW	3390	3400
Sand(5BW)	212	220	Bl. Sla.	2105	2140	Shale	3400	3405
Red Rock	220	790	Sandy Li	2140	2193	equals 3425	Steel line corr.	
Gray Slate	790	993	Bl. Sla.	2193	2215	Shale	3405	3422
Salt	993	1010	Lime	2215	2227	Sdy Lime	3422	3425
Blue Slate	1010	1040	Bl. Sla.	2227	2295	Lime	3425	3430
Salt	1040	1075	Lime	2295	2305	Shale	3430	3477
Blue Slate	1075	1095	Bl. Sla.	2305	2330	Lime Shells	3477	3485
Salt	1095	1125	Lime	2330	2342	Lime	3485	3493
Sandy Shale	1125	1390	Dk. Shale	2342	2355	Red & Green Sh.	3493	3495
Blue Shale	1390	1400	Lime	2355	2358	Lime 2BW	3495	3632
Lime	1400	1430	Dk. Shale	2358	2369	Sand HFW	3632	3642
Salt & Sh	1430	1455	Lime	2369	2375	Lime	3642	3670
Lime	1455	1475	Bl. Sla.	2375	2395	Shale	3670	3677
Blue Slate	1475	1480	Sand HFW	2395	2422	Lime HFW	3677	3780
Lime	1480	1490	Bl. Sla.	2422	2455	Blk Shale	3780	3790
Blue Slate	1490	1505	Lime	2455	2465	Broken Lime	3790	3800
Lime	1505	1525	Bl. Sla.	2465	2530	Lime	3800	3868
Blue Slate	1525	1540	Lime	2530	2555	Shale	3868	3890
Lime	1540	1560	Sdy Sh.	2555	2605	Lime	3890	3895
Blue Slate	1560	1572	Lime	2605	2625	Shale & Shells	3895	3907
Lime	1572	1580	Bl. Sla.	2625	2630	Lime	3907	3955
Blue Slate	1580	1600	Lime	2630	2705	Shale	3955	3958
Lime	1600	1655	Bl. Slate	2705	2710	Show gas & Oil	Rainbow	
Blue Slate	1655	1660	Lime	2710	2715	Lime	3958	4004
Red Rock	1660	1670	Bl. Sla.	2715	2730	Sh Oil	3982	
Sand Lime	1670	1695	Lime	2730	2755	Cherty Li.	4004	4008
Blue Slate	1695	1700	Bl. Sla.	2755	2765	Chat	4008	4037
Red Rock	1700	1740	Lime	2765	2775	Chert & Li	4037	4044
Blue Slate	1740	1745	Blue Sh.	2775	2795	1 BW Sm Sh Oil		
Lime	1745	1830	Sand 3BW	2795	2835	Lime & Ch	4044	4050
Dark Slate	1830	1840	Lime	2835	2843	Dk Sh	4050	4174
Sandy Lime	1840	1855	Sand HFW	2843	2863	Lime	4174	4198
Sand 1/5 BW	1855	1865	Lime	2863	3050	Shale	4198	4237
Lime	1865	1880	Sand	3050	3060	Lime HFW	4237	4337
Red Rock	1880	1884	Lime	3060	3095	Shale	4337	4338
Lime	1884	1888	Sdy. L. HFW	3095	3100	Sdy Lime	4338	4343
Blue Slate	1888	1912	Lime	3100	3166	Lime	4343	4353
Lime	1912	1925	Sla. & Shells	3166	3200	Sand	4353	4367
Red Sh	1925	1932	Lime	3200	3260	Sdy Lime	4367	4375
Lime	1932	1950	Blue & Blk Sla.	3260	3277	Shale	4375	4412
Bl. Slate	1950	1963	Lime	3277	3288	Gr. Sh	4412	4415
Lime	1963	1977	Blk & Blu Sla.	3288	3292	Lime HFW	4415	4420
Gray Sl.	1977	1981	Gray Slate	3292	3305	BOTTOM		
Red Rk	1981	1993	Lime	3305	3310			
Lime	1993	1995	Sdy Shale	3310	3365			

The information given above is a complete and correct record of the well and all work done thereon.

BY A. L. Privett  
R. E. Garden & Son  
by Jack Garden

Subscribed and sworn to before me, a Notary Public, Reno County, Kansas on the 21st day of May, 1935.

My Commission Expires November 4, 1935.

Ruth Richens N.P.

RECEIVED  
JUN 1 1969  
BY *JmC*

BOOK PAGE  
DATE REC.  
1969

R. E. GARDEN & SON

DRILLING CONTRACTORS

AUGUSTA, KANSAS

May 17 1935.

*Have bill - ✓  
Billed  
Plugging record*

*6-3-*

*15-155-39381-0000*

Mr. T.A. Morgan,  
800 Bitting Building,  
Wichita, Kansas.

PLUGGING		
FILE	SEC. 27	T. 26 R. 10 W.
BOOK	PAGE 5	LINE 47

Dear Sir:

We wish to abandon well known as  
the Crotts #1, located in Section 27, Township  
26, Range ~~26~~ West, Reno County, Kansas.

*10*

Yours very truly,

*R. E. Garden Sr.*  
R. E. Garden, Sr.

R. E. Garden & Son,  
1119 Ohio St.  
Augusta, Kansas