

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21195-0000

LEASE NAME Brensing "B"

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4720 Ft. from N Section Line

3800 Ft. from W Section Line

SEC. 27 TWP. 27S RGE. 19 (X) or (W)

COUNTY Kiowa

Date Well Completed 1/9/86

Plugging Commenced 7/12/00

Plugging Completed 7/14/00

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

PHONE#(316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top _____ Bottom _____ T.D. 4875'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISS

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	439'	-0-
				5 1/2	4874'	2986-48'

AUG 4 2000

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Set cast iron bridge plug @ 4400'/w/5 sx cement on top. Shot pipe @ 3000' pull to 1250'; pumped 11 sx gel & 50 sx cement; pumped 50 sx ANT 450'; circulate 10 sx cement @ 40' All cement 60/40 Posmix/w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike Kelso License No. 31528

Address PO Box 467 - Chase, Ks. 67524-0467

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (Employee of Operator) or (Operator)-of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D
Wichita, Ks. 67205

SUBSCRIBED AND SWORN TO before me this 1st day of August, 2000

Judith K. Moser
Judith K. Moser Notary Public

Commission Expires: May 17, 2001

