


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kiowa County, Sec. 11 Twp. 27S Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Mull Drilling Company, Inc.  
Lease Name Miller Well No. 1  
Office Address 6405 East Kellogg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 4, 1956 19  
Application for plugging filed April 4, 1956 (Verbal) 19  
Application for plugging approved April 4, 1956 (Verbal) 19  
Plugging commenced April 4, 1956 19  
Plugging completed April 5, 1956 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4932 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	408'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 400 feet. Set bottom plug, 1/4 sacks hulls and 20 sacks cement. Filled with mud to 35 feet. Set top plug, 1/4 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Drilling Company  
Address 1005 East Second, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. A. Mull, Jr. (employee of owner) or (owner or contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
6405 East Kellogg, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12<sup>th</sup> day of April, 1956

My commission expires Jan. 28, 1957  
Ethel Zimmerman Notary Public.

PLUGGING  
FILE SEC 11 T 27 R 19W  
BOOK PAGE 51 LINE 32

APR 17 1956 4-17-56

NO. 1 MILLER

WELL LOG

Location: NE NE SE, 11-27S-19W  
Kiowa County, Kansas  
Operator: Mull Drilling Company, Inc.  
6405 East Kellogg, Wichita, Kansas  
Contractor: Graham-Messman-Rinehart Drilling Co.  
1005 East Second, Wichita, Kansas  
Commenced: March 20, 1956  
Completed: April 5, 1956  
Elevation: 2243 KB  
Production: D&A  
Casing Record: 8 5/8" set at 408' w/300 sacks cement

.....L O G.....

Sand	230
Clay-Shale	250
Shale-Shells	320
Shale	520
Sand	555
Shale	620
Sand	641
Shale	645
Shale-Shells-Red Bed	672
Anhydrite	689
Shale-Shells	875
Shale-Shells-Red Bed	1390
Shale-Red Bed	1490
Shale-Shells	1885
Salt-Shale	2000
Shale-Lime	2325
Lime	2605
Lime-Shale	2730
Lime	2970
Lime-Shale	3405
Lime	3585
Lime-Shale	3745
Shale-Lime Streaks	3828
Lime	4795
Lime-Chat	4805
Cherty Lime	4820
Lime-Chert	4920
Lime	4932 R.T.D.

Sample Tops:


Heebner 4056 (-1813)  
Brown Lime 4206 (-1963)  
Lansing 4213 (-1970)  
Cherokee Sd 4775 (-2532)  
Mississippi 4796 (-2553)  
Kinderhook 4918 (-2675)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By:   
J. A. Gilliland

Subscribed and sworn to before me  
this 10th day of April 1956.

  
Notary Public

My Commission Expires: November 5, 1958

