

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sedgwick SEC. 36 TWP. 25S RGE. 1 XX/W
Location as in quarters or footage from lines:
1680' FWL & 990' FNL SE/4

Lease Owner Lachenmayr Oil Co.
Lease Name Royal Incorporated Well No. 1
Office Address 1125 N. Main, Newton, Ks. 67114
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 3/8/82
Application for plugging filed 3/8/82
Plugging commenced 3/8/82
Plugging completed 3/8/82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation _____ Depth to top _____ bottom _____ T.D. 3473'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	238'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 260', 1 sack hulls, plug, 30 sacks cement
Mud to 60', 1/2 sack hulls, plug, 20 sacks cement.
5 sacks cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita,
(Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1982

Carolyn J. Tjaden
Carolyn J. Tjaden -- Notary Public.

My Commission expires:



DRILLERS LOG

Lachenmayr Oil Company
 OPERATOR: 1125 N. Main, Newton, Ks. 67114
 CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042**
 Lease Name Royal, Incorporated Well No. 1
 Sec. 36 T. 25S R. 1W Spot. 1680' FWL & 990' FNL SE/4
 County Sedgwick State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 238' with 140 Sxs.
 Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 3473'

Drilling Commenced: 3/1/82 Drilling Completed 3/8/82

Formation	From	To	Tops
Cellar	0	7	Lansing - 2328
Sand, Shale, Lime	7	732	Kansas City - 2565
Shale, Lime	732	1044	Marmaton - 2791
Shale, Lime, Sand	1044	1377	Mississippi - 3057
Lime, Shale	1377	2170	Kinderhook - 3346
Shale, Lime	2170	2328	Viola - 3447
Lime	2328	2422	
Lime, Shale	2422	2510	
Shale, Lime	2510	2565	
Lime	2565	2743	
Shale	2743	2791	
Lime	2791	2987	
Lime, Shale	2987	3057	
Lime	3057	3346	
Shale	3346	3447	
Lime	3447	3473	

RECEIVED
 STATE CORPORATION COMMISSION
MAR 12 1982
 CONSERVATION DIVISION
 Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log _____ Type and Depths Covered _____

