


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 1 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mull Drlg. Co. Inc.

Complete Address 415 Page Court 224 W. Douglas Wichita, Ks

Lease Name Einsel H Well No. 1

Location C NE/~~SE~~NE Sec. 5 Twp. 27 Rge. 20 (E) (W)W

County Kiowa Total Depth 4843

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering Co. Inc.

Address Box 698 Great Bend, Ks License No. 670

Operation Completed: Hour 1:00 PM Day 30 Month 8 Year 1972

The above well was plugged as follows:

577 ft 8 5/8 surface pipe cemented with 275 sacks. 4827 ft 4 1/2 long  
string cemented with 150 sacks. Open hole. Sand to 4800 ft, 4 sacks  
cement with bailer. Pulled 3600 ft 4 1/2. Set 10 ft rock bridge at  
300 ft with 35 sacks cement. Mud to 40 ft, plug, 15 sacks cement  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9/1/72

INV. NO. 6263-W