

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill,
filed May 31, 1967.

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Einsel "G" Well No. # 1

Location C SE NW Sec. 20 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 4970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Walters Drilling Company

Address 400 Insurance Bldg., Wichita, Kansas License No.

Operation Completed: Hour 10:00 P.M. Day 13th Month June Year 1967

The above well was plugged as follows:

369' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid
level in the hole was at 350', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 350', and cemented with
23 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1 sack of dry cement, and 1/2 sack of hulls on fluid at 40',
and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 6/16/67
INV. NO. 5401-W