

RECEIVED

AUG 07 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

15-095-20912-00-80

WELL PLUGGING APPLICATION FORM
PLEASE TYPE FORM and File ONE Copy)

API # 12-20-1979 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419
(owner/company name) (operator's)

ADDRESS P.O. Box 438 CITY Haysville

STATE KS ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE Graber WELL# 1 SEC. 4 T. 27 R. 6 (East/West)

C - SE - NW SPOT LOCATION/0000 COUNTY Kingman

3300 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

3300 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 292' CEMENTED WITH 275 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4082 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4084-86' OH 3760-66' CIBP 3430 - 3410-12

ELEVATION 1508 T.D. 4086 PBD 3430 ANHYDRITE DEPTH ?
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Dump sand to 3360', dump bail 4 sax cement on sand, pull pipe, spot 35 sax at 900', 35 sax at 450', circulate cement from 342' to surface.

60/40 poz 4% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Schremmer PHONE# (316) 524-1225

ADDRESS P.O. Box 438 City/State Haysville, KS 67060

PLUGGING CONTRACTOR Gressel Oil Field Service, Inc. KCC LICENSE # 30084
(company name) (contractor's)

ADDRESS P.O. Box 607, Burrton, KS 67020 PHONE # (620) 463-5161

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-6-03 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

6/04

6/04

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bear Petroleum, Inc.
PO Box 438
Haysville, KS 67060

August 08, 2003

Re: GRABER #1
API 15-095-20912-00-00
SENW 4-27S-6W, 3300 FSL 3300 FEL
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely



David P. Williams
Production Supervisor