

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22403-00-00
Spot: NENE Sec/Twnshp/Rge: 4-30S-15W
4488 feet from S Section Line, 639 feet from E Section Line
Lease Name: LEE F Well #: 1
County: BARBER Total Vertical Depth: 4828 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 4.5 | 4634 | 2230 | WITH 150 SX CMT |
| SURF | 8.625 | 271 | | WITH 185 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/25/2015 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP BOTTOM WITH 200# HULLS & 25 SX CMT. PLUG AT 840' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2015 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT. SHUT-IN PRESSURE 1000#. TOC @ 3950'. 1ST PLUG AT 846' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 317' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4512 | 4517 | | |

KCC WICHITA
SEP 14 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)
5A

RECEIVED
SEP - 3 2015
KCC DODGE CITY