

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21294-00-00
Spot: S2NESENW Sec/Twnshp/Rge: 11-10S-26W
1875 feet from N Section Line, 2310 feet from W Section Line
Lease Name: BITTEL Well #: 1-11
County: SHERIDAN Total Vertical Depth: 4153 feet

Operator License No.: 3581
Op Name: RED OAK ENERGY, INC.
Address: 7701 E KELLOGG DR STE 710
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4153		175 SX
SURF	8.625	252		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/03/2015 8:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DAVE PAULEY Company: RED OAK ENERGY Phone: (316) 650-7625

Proposed Plugging Method: Ordered 450-sx 60/40 pozmix 4% gel cement w/500 # hulls and 1000 # gel.
PC at 2252' w/325 sx CWC
Production perforations: 3953' - 4074'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/03/2015 12:40 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3950'. Global pumped 1000 # gel followed by 50 sx cement w/150 # hulls.
Pulled tubing to 2650' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 1421' and pumped 200 sx cement. Cement circulated. PTOH. Topped casing off w/15 sx cement.
Casing full. Hooked on to backside and pumped 15 sx cement. Maximum pressure 300 psi.
Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
4052	4056		
4010	4016		

Remarks: GLOBAL CEMENT
Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN) CM

SEP 08 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS