

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-013-20046-00-00  
Spot: NWSENESW Sec/Twnshp/Rge: 15-1S-15E  
1800 feet from S Section Line, 2170 feet from W Section Line  
Lease Name: PLATTNER Well #: 11-15  
County: BROWN Total Vertical Depth: 3400 feet

Operator License No.: 33397  
Op Name: RUNNING FOXES PETROLEUM INC.  
Address: 6855 S HAVANA ST. STE 400  
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	272		165 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2015 4:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DUKE COULTER Company: C & G DRILLING Phone: (620) 583-4306

Proposed Plugging Method: TD 3400': 50' plug at 3295', 50' at 2245', 50' at K.C., fill 310' to 210' rat and mouse hole top 50' to surface.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 05/01/2015 5:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

HAD DRILL PIPE RAN DOWN TO 3295' INSIDE THE SURFACE CASING AND PUMPED 25 SACKS OF CEMENT. PULLED THE DRILL PIPE UP TO 2245' AND PUMPED 25 SACKS OF CEMENT. PULLED THE DRILL PIPE UP TO 1034' AND PUMPED 25 SACKS OF CEMENT. PULLED THE DRILL PIPE UP TO 310' AND PUMPED 35 SACKS OF CEMENT. PUT 15 SACKS OF CEMENT IN THE RAT HOLE AND 10 SACKS OF CEMENT IN THE MOUSE HOLE.

Perfs:

KCC WICHITA  
SEP 08 2015  
RECEIVED

RECEIVED  
KCC DIST # 3  
SEP 03 2015  
CHANUTE, KS

TH

Remarks:

Plugged through: DP

District: 03

Signed

Taylor Herman

(TECHNICIAN)