

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-24130-00-00  
Spot: SESWSWSE Sec/Twnshp/Rge: 3-35S-10W  
155 feet from S Section Line, 2243 feet from E Section Line  
Lease Name: REGGIE 3510 Well #: 1-3  
County: BARBER Total Vertical Depth: 5515 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5130		WITH 50 SX CMT
COND	20	80		WITH 5 SX CMT
PROD	7	5512	1327	WITH 610 SX CMT
SURF	9.625	811		WITH 460 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/10/2015 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5120' WITH 5 SX CMT. PLUG AT 860' WITH 75 SX CMT. PLUG AT 300' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/10/2015 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 5130' & SPOTTED 50 SX CMT ON TOP OF CIBP THROUGH TBG. LOAD HOLE WITH DRILLING MUD. 1ST PLUG AT 860' WITH 75 SX CMT. 2ND PLUG AT 315' TO SURFACE WITH 115 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5170	5184		

KCC WICHITA  
SEP 14 2015  
RECEIVED

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
AUG 19 2015  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)