

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21971-01-00
Spot: NENWNENE Sec/Twnshp/Rge: 23-34S-6W
200 feet from N Section Line, 850 feet from E Section Line
Lease Name: DONNA MAE 3406 Well #: 1-23H
County: HARPER Total Vertical Depth: 5031 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 SX
II	7	5639		370 SX
PROD	4.5	9510	1525	0 SX
SURF	9.63	655		365 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2015 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPL Phone: (405) 429-6536

Proposed Plugging Method: CIBP @ 4330' & 10 SKS CEMENT. 701' WITH 50 SKS. 451' & CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 08/26/2015 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4334' & CAPPED WITH 10 SKS CEMENT. RAN TUBING TO CIBP & CIRCULATE MUD INSIDE 7" CASING. CIRCUALTE 10 SKS CEMENT ON TOP OF CIBP. REC 1525' & 7" CASING AND LAYED DOWN. RAN TUBING TO 701' SPOTTED 50 SKS CEMENT. PULLED TUBING TO 451' & CIRCUALTE CEMENT TO SURFACE WITH 250 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
9196	9382	CSG	
8771	9104	CSG	
8473	8673	CSG	
8046	8375	CSG	
7598	7950	CSG	
7238	7510	CSG	
6953	7188	CSG	
6478	6830	CSG	
6084	6410	CSG	
5698	9382	CSG	
5241	5441	CSG	

KCC WICHITA
SEP 15 2015
RECEIVED

Remarks: ORR ENTERPRISES CLASS "C" CEMENT. TMD = 9510

Plugged through: TBG

District: 02

Signed _____


(TECHNICIAN)