

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22753-01-00
Spot: SENENWNE Sec/Twnshp/Rge: 18-34S-4W
500 feet from N Section Line, 1554 feet from E Section Line
Lease Name: SUBERA 3404 Well #: 2-18H
County: SUMNER Total Vertical Depth: 4492 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	100		13 SX
II	7	5251		340 SX
PROD	7	4485	953	340 SX
SURF	9.625	565		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2015 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPL. Phone: (580) 430-4500

Proposed Plugging Method: CIBP @ 4720' & 10 SXS. 50 SXS @ 950', 50 SXS @ 602'. CIRCUALTE 305 WITH 100 SKS CEMENT.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/31/2015 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4720'. TRIPPED TUBING IN HOLE TO LOAD HOLE WITH MUD. SPOTTED 10 SKS CEMENT ON BP. LAYED DOWN TUBING. REC'D CASING FROM 953' AND LAYED OUT. RAN TUBING TO 950' SPOTTED 50 SKS CEMENT. PULLED TUBING TO 602', SPOTTED 50 SKS CEMENT. PULLED TUBING TO 305' & CIRCUALTED CEMENT TO 0' WITH 100 SXS CEMENT.

Perfs:


Top	Bot	Thru	Comments
8663	8885	CSG	
8318	8605	CSG	
7953	8250	CSG	
7573	7870	CSG	
7228	7510	CSG	
6866	7175	CSG	
6483	6783	CSG	
6133	6415	CSG	
5730	6045	CSG	
5320	5635	CSG	
4798	8885	CSG	

KCC WICHITA
SEP 15 2015
RECEIVED

Remarks: ORR ENTERPRISES CLASS "C" CEMENT. TMD = 9001

Plugged through: TBG

District: 02

Signed 
(TECHNICIAN)

JK