

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-203-20219-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 19-19S-35W
4430 feet from S Section Line, 4743 feet from E Section Line
Lease Name: REES RANCH Well #: 4-19
County: WICHITA Total Vertical Depth: 5250 feet

Operator License No.: 34319
Op Name: SDOCO, LLC
Address: PO BOX 369
LITTLETON, CO 80160

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2900		WITH 20 SX CMT
PROD	5.5	3180	0	WITH 530 SX CMT
SURF	8.625	349		WITH 215 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/25/2015 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: MONTIE GREER Company: SDOCO, LLC Phone: (303) 979-4029

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2015 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2900' WITH 20 SX CMT. PUMP 50 SX CMT WITH 200# HULLS AT 2300' TO 1800'. PUMP 135 SX CMT AT 1288' TO 0'. TOOH WITH TBG & TOP OFF WITH 6 SX CMT. PUMP 3 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
1845	2315		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed 
(TECHNICIAN)

RECEIVED
SEP - 8 2015
KCC DODGE CITY MP

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 18 2015
CONSERVATION DIVISION
WICHITA, KS